

# WHEN ORDERING:

V. March 01, 2008

**SHEARMAX™** panels are typically sold through most major lumberyards and/or hardware supply companies and does not sell direct to end-users.

When ordering please reference our company name:

**Shear Transfer Systems, Inc. or our DBA: SHEARMAX'**

**NOTE: Many retailers list us by our corporate name and not our dba 'SHEARMAX'**

Panels are sold in 1-foot height increments and custom height panels are available at no additional charge with minimal lead-time, however, custom panels are not returnable. No retailer receives special pricing and no minimum order is required. We do offer the knowledge that our wholesale prices are usually under other panel manufactures, and that we offer the best value of dollar to load possible, wood or steel. We set no retail pricing, so prices may vary and it may be good to shop around.

Panels, reusable templates, and hold-down anchor bolts are all sold separately not as kits. Each and every panel from the foundation to top of panel requires the following proprietary items:

- 1 Reusable Template
- 2 Hold-down Anchor Bolts
- 1 Panel

The reusable template and foundation bolts are usually ordered by whoever is doing the concrete work.

Templates are reusable.

Hold-down Anchor Bolts come complete with A449 stud, coupler and large 1 ½" embedded nuts.

Standard bulk 5/8" x 10" min "L" bolts are needed for shear anchorage but are not supplied by SHEARMAX.

Panels are usually ordered by whoever is buying the lumber.

Panels come with necessary hardware for a typical connection to the foundation and top of panel (except nails).

Please refer to attached Reference List for diagrams and model codes.